

ProTech Services LLC

Fume Hoods:

- Tested to manufacturer and ANSI specifications.
- Depending on type of hood, testing to include:
 - Sash inflow (FPM/CFM),
 - Smoke inflow,
 - Smoke clearance time,
 - Inspection of installation & proper use,
 - Ground polarity check.
- Optional tests or services can include (if applicable):
 - Application of in-house and SAMA specifications,
 - Vertical & horizontal cross draft profiles,
 - Motor & belt inspection,
 - HEPA Filter leak testing & repair or replacement,
 - Light intensity (UV & UVC),
 - Sound levels,
 - Vibration measurements,
 - ASHRAE 110 testing available upon request.